

it's what's underneath that counts $\ensuremath{\mathbb{R}}$

	1. Make sure the subfloor is structurally sound, level and is free of dust and debris. 2. Check for protruding nails and/or defects in the subfloor. If installing over concrete, the concrete must be dry with moisture emission rates that do not exceed 3 lbs. per 1000 square feet per 24 hours as measured by the Anhydrous Calcium Chloride Test.
2	 Start in a corner with the tape strip side next to the wall and the overlapping film toward the open room. Install floorMuffler® UltraSeal (film side down) parallel to the wall in the opposite direction that you plan to install the flooring planks. When installing the floorMuffler® UltraSeal, leave at least 2" going up the wall.
3	 Be sure to unfold the film, extending it 3" from the foam. Roll out the next roll of floorMuffler® UltraSeal in the same manner, making sure that the foam seams are butted together. Be sure to overlap only the moisture barrier lip and not the foam pad.
	1. Remove the adhesive liner and adhere the foam to the film overlap.
5	1. Install the flooring per manufacturer's instructions.

For glue down installations, always follow the adhesive manufacturer's instructions. Make sure to use a floorMuffler approved adhesive. The list of approved adhesives can be found on each product page on the floorMuffler website.







floormuffler.com 1 800 440 6008